

50' MBGF (centered on structure)
with an SGT Type I on either end.
Total length: 150'

100' MBGF (centered on structure)
with an SGT Type I on either end.
Total length: 200'

25' MBGF (centered on structure)
with an SGT Type I on either end.
Total length: 125'

25' MBGF (centered on structure)
with an SGT Type I on either end.
Total length: 125'

Contractor responsible for obtaining all necessary permits.

Contractor shall coordinate with Digtess and provide all necessary utility adjustments for any existing underground utilities accordingly.

Where existing pavement does not exist, Contractor shall install mow strip in accordance with TxDOT Standard GF(31)MS-11.

Contractor shall install MBGF in accordance with TxDOT Standard MBGF-11.

Contractor shall install SGT in accordance with TxDOT Standard SGT(7)31-11 Type I.